



111 Pioneer Industrial Drive
Mayfield, KY 42066
Phone: 270-247-1400 Fax: 270-247-1488

4/15/20

Re: 23 Homer Lucas Lane Septic Tank with alarm

Yec proposes to supply labor, materials, and equipment to complete the following scope of work.

Septic Tank Installation

\$8,500.00

- Install south of the building in the open lot area
- Install one 1000 gallon septic tank
- Install the pump alarm
- Install stacking rings or small precast barrel from the tank access to grade for pumping
- Install bollards near tank access for protection

Sanitary Laterals

\$6,500.00

- Install approximately 160' of 4" PVC
- Install one 4" wye to connect lines from the east and west
- Install stone backfill and spoil removal in improved areas

Electric and Alarm

\$3,000.00

- Install approximately 150' of conduit and wire to energize the alarm and floats
- Furnish and install high water floats

*This quotation is based to include all items above for a complete system
Asphalt or concrete demo or replacement is not included in this quotation
This quotation is based to include tie in to the existing stubouts outside the building*

Thank you for the opportunity to submit this quotation and we look forward to working with you again.

Sincerely,

A handwritten signature in blue ink that reads 'Kevin Kell'.

Kevin Kell

Youngblood Excavating & Contracting, LLC