



6/10/2021

True Line Roofing is pleased to submit the following proposal for work on the east and west side gutter system at 1101 Main Street Benton, KY 42025. This price is to furnish all labor, material, and equipment needed to perform the following work, with exception to any additional agreed upon changes or upgrades.

Scope of work

- Remove any termination bar and fasteners used to secure the existing EPDM membrane.
- Remove the EPDM membrane along with any built-up tar and adhesives on the wall.
- We will inspect the substrate for any damage and if needed, we will advise on any necessary changes.
- Fully adhere new 45 mil Mule Hide TPO to the substrate in the gutter system.
- Continue the new TPO up the wall past the old tar/caulking.
- Using water cut off mastic and sealant we will terminate the TPO to the brick wall with metal termination bar.
- Cut a groove in the brick above the termination bar in order to install metal counterflashing that extends over the new membrane and ensures a watertight seal.
- On the outside edge we will install a metal drip edge to terminate the TPO and create a watertight seal.
- We will provide trained safety personnel on the ground, street, and roof. In addition to, trained equipment operators.
- This proposal is good for 30 days due to market volatility.

Total Price: \$19,376.00

We appreciate you considering us as a potential partner for your roofing and construction needs.

Erick Young

270.226.4258
731.363.2251
erick@truelinebuilder.com

2687 US HWY 641 N
BENTON, KY 42025